



CHANDRAPUR MUNICIPALITY

Office of Municipal Executive

Chandranigahpur, Rautahat

चन्द्रनिगाहपुर, रौतहट
मधेश प्रदेश, नेपाल

BID ADDENDUM NOTICE

Date of publication: 2081/02/25

This is to notify all the concerned bidders that addendum has been made for Contract ID CM/WORKS/NCB/04/2080/081 i.e, "Construction of a part of main building block at Chandranigahpur Hospital" published on 2081/02/02. The addendum can be downloaded from PPMO portal <https://www.bolpatra.gov.np/egp> or Chandrapur Municipality portal <https://chandrapurmun.gov.np/>.

किरण निधि तिवारी
प्रमुख प्रशासकीय अधिकृत

Following changes are made in the bid document:

Sl. No	Existing Criteria	Modified Criteria	Latest Criteria Description
1.	Bid Security : 10,45,000.00	Bid security of 14,20,000.00	
2.	Minimum average annual construction turnover	Minimum average annual construction Turnover of NRs 5.40 crore	Minimum average annual construction turnover of NRs 5.40 crore calculated as total certified payments received for construction contracts in progress or completed, within best three years out of last ten years.
3.	Completion time : 1 year from the date of agreement	Completion time : 1 year from the date of agreement	Completion time : 1 year from the date of agreement
4.	Bill of quantities	For details look into BOQ from Bid addendum from PPMO portal https://www.bolpatra.gov.np/egp	For details look into BOQ from Bid addendum from PPMO portal https://www.bolpatra.gov.np/egp

[Handwritten signature] *[Handwritten signature]*

[Handwritten signature]
किरण निधि तिवारी
 प्रमुख प्रशासकीय अधिकृत

Bid Addendum Report



Chandrapur Municipality, Rautahat

Chandrapur Municipality, Rautahat
Chandrapur, Rautahat
Rautahat
Province Two
Nepal

Addendum No: 1

Published On: 07-06-2024 21:00

Invitation No: CM/WORKS/NCB/04/2080/081

Dated On: 15-05-2024 07:10

Chapter: Bid Data Sheet


Sl. No.	Relevant Clause No / Name	Existing Clause	Modified Clause
1	ITB 19.1	The Bidder shall furnish a bid security from "A" class commercial bank. Which shall be valid for 30 days beyond the validity period of the bid. []	The Bidder shall furnish a bid security from "A" class commercial bank. Which shall be valid for 30 days beyond the validity period of the bid. []

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
किरण निधि तिवारी
प्रमुख प्रशासकीय अधिकृत

Chapter: Evaluation and Qualification Criteria



Sl. No.	Existing Criteria	Modified Criteria	Latest Criteria Description
1	Other Eligibility : Additional requirements	Other Eligibility: Completion time : 1 year from the date of agreement (EQC automatically removed, so inserted completion time here)	(EQC (ITB 13.2 automatically removed from the system, so attached completion time is here.) If any clause on completion time is seen in Bid bid addendum, the latest modified clause for completion time is 1 year only. Other clauses mistakenly generated about Completion time below is not counted
2	Average Annual Construction Turnover	Average Annual Construction Turnover	Minimum average annual construction turnover of NRs 5.40 crore calculated as total certified payments received for construction contracts in progress or completed, within best three years out of last ten years. Only the net amount shall be calculated after deducting the amount for VAT and such amount shall be adjusted wholesale price index of Nepal Rastra Bank. For Single Entity : Must meet requirement For joint Venture : All combined partner Must meet requirements, Each partner Must meet 3 of the requirement, One partner must meet 4 of the requirements. Documents Submission Requirements : Form FIN -2 Only the net amount shall be calculated after deducting the amount for VAT and such amount shall be adjusted to present value by applying wholesale price index of Nepal Rastra Bank. Note: (2) The amount stated should normally not be less than $1.5 \times V/T$, the estimated annual turnover in the subject contract based on a straight-line projection of the Employer's estimated cost (V), over the contract duration (T) in year. Contract duration less than one year shall be considered one year. The multiplier of 1.5 may be reduced up to 1 (one) in accordance with the size, nature and complexity of contracts. (3) Usually not less than 25 % (4) Usually not less than 40 %
3	Alternative Technical Solutions	Multiple Contracts - NA	Multiple Contracts, if permitted under ITB 35.4, will be evaluated as follows: Award Criteria for Multiple Contracts [ITB 35.4]: Bidders have the option to Bid for any one or more Contracts. Bids will be evaluated taking into account discounts offered, if any, for combined contracts. The contract(s) will be awarded to the Bidder or Bidders offering the lowest evaluated cost to the Employer for combined contracts, subject to the selected Bidder(s) meeting the required qualification criteria for combination of multiple contracts as the case may be.

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
[Official stamp]

Sl. No.	Existing Criteria	Modified Criteria	Latest Criteria Description
			<p>Qualification Criteria for Multiple Contracts: The criteria for qualification shall be the sum of the minimum requirements for respective individual contracts as specified under items 2.3.2, 2.3.3, 2.4.2 b, 2.5 and 2.6. With respect to the Contracts of Similar Size and Nature under item 2.4.2(a). of Section III, the evaluation shall be done as below: N is the minimum number of contracts required as per Specific Construction Experience (2.4.2(a)). V is the minimum value of a single contract as per Note (2), (3) or (4) of 2.4.2 Specific Construction Experience</p> <p>i. Minimum requirements for combined contract(s) shall be the aggregate requirements for each contract for which the bidder has submitted bids as follows, and N1,N2,N3, etc. shall be different contracts: Contract 1: N1 contracts, each of minimum value V1; Contract 2: N2 contracts, each of minimum value V2; Contract 3: N3 contracts, each of minimum value V3; ---etc.</p> <p>Or</p> <p>ii. Total number of contracts is equal or less than $N1 + N2 + N3 + \dots$ but the total value of all such contracts is equal or more than $N1 \times V1 + N2 \times V2 + N3 \times V3 + \dots$.</p>
4	Alternative Technical Solutions	In case other than Multiple Contracts	Bidders have the option to Bid for any one or more Contracts. The contracts will be awarded to the Bidder or Bidders offering the lowest evaluated cost to the Employer, subject to the selected Bidder(s) meeting the required qualification which shall be the sum of the minimum requirements for respective individual contracts. Under this case, Contract shall be awarded based on Least Cost Combination to the Employer.
5	Completion Time - one year from the date of agreement	Removed	An alternative Completion Time, if permitted under ITB 13.2, will be evaluated as follows: [insert project specific requirements]

Chapter: Bill of Quantities

1 Provisional Sum					
Procurement Item Details					
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Insurance coverage for loss or damage to the works, plant, Equipment, Materials other property, personal injury or death insurance for the Contractor's employees and for other people as per GCC 19.1	P.S.	1	213338	213338

Procurement Item Details					
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
2	Carrying out different laboratory tests of construction material like cement, rod, sand, aggregate, filling materials, concrete cubes etc. during construction work as per specification and direction of Site Engineer.	P.S.	1	60000	60000
3	PROJECT INFORMATION BOARD: Supplying and installation of information board specifying brief of project as per specified size, shape and other details all complete.	P.S.	1	5000	5000

2 Construction work

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	SITE CLEARANCE AND LAYOUT Clearing the site by removing the bushes, trees, concrete pavement and hard surface whatever at site up to its root depth including the layout work, marking the trench, construction of permanent reference points along each grid precisely in line and level and including construction of all necessary staff and labor facilities.	Sq.m	1200.0			
2	EARTHWORK IN EXCAVATION Excavation in foundations in all type of soils for foundation, trenches, footing, pits etc. to the required depth including dewatering by manual or mechanical means etc. as per specifications with all contractor's own machinery and equipment's, providing crossing of track, shoring, strutting, timbering and buttressing with appropriate materials and all such measures necessary to retain in position the sides of the foundation pit and including refilling the excavated material with watering, ramming, leveling the site and disposing off the surplus/unusable earth to outside the construction premises, etc. all complete as per drawings, specifications and instructions of the Engineer.	Cu.m	871.21			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

77
संयुक्त निर्माण विभाग
लुगुन महानगर अस्पताल

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
3	EARTHBACK FILLING Back filling in foundation and sides of foundation with approved soil obtained from the excavation at site and stacked at site or brought from outside in layer not exceeding 15 cm thick (compacted thickness) including transportation of soil, spreading in required line and level, sprinkling water, ramming, compacting with mechanical rammers, testing, etc., all complete as per drawing, specification and instructions of the Engineer.	cu.m.	671.55			
4	SAND FILLING Filling 2" sand in floor by sprinkling of water and compaction by labour including lead from 30 m distance as per drawing specification and instruction of the Consultant/Engineer all complete.	cu.m	58.4			
5	500 MICRON POLYTHIENE SHEET Supplying and laying 500 micron tear proof good quality polythene above the compacted stone soling. The overlapping of the sheet must be more than 230mm in all side to prevent moisture through it. The cost should be inclusive of all material and labour cost, as per design drawing, specification and instruction of the Engineer, all complete.	sq.m	1167.91			
6	Flat Brick Soling work Providing and laying, dry brick soling in floor with first class chimney made bricks complete to level including sand filling on joints, as per drawing, specification and instruction of engineer, all complete.	Sq.m	611.03			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
किरण निधि निवारी
मुख्य प्रशासकीय अधिकारी

Procurement Item Details						
Sl. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
7	<p>REINFORCED BRICKWORK (1:4:3)</p> <p>Providing and laying first class local chimney made brick one or more brick thick wall in cement mortar 1:4:1 cement : 4 coarse sand) in superstructure in all heights and level including the cost of single or multi stage self standing scaffolding, soaking bricks, curing, raking joints, provision for recesses, openings, toothing etc., all complete as per drawing, specifications and instructions of the Engineer.</p>	Cu.m	445.5			
8	<p>P.C.C (1:3:6) Works</p> <p>Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:3:6 (1 cement : 3 sand : 6 coarse aggregate) for leveling course in foundations and under floor of building, etc. in all level with broken stone aggregate of size not more than 25 mm of approved quality including formwork wherever necessary, dewatering, batching, mixing, transporting, placing, compacting, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.</p>	cu.m	154.67			
9	<p>P.C.C. FOR R.C.C. WORKS</p> <p>Providing and laying in position machine mixed and machine vibrated cement concrete of mix 1:1.5:3 (1 cement:1.5 sand: 3 coarse aggregate) M20 grade for reinforced cement concrete work using approved cement with 20 mm graded machine crushed stone aggregate of approved quality in various locations and heights including transportation of concrete to site of placing, compaction, finished to required line and level, protection and curing, etc. all complete as per drawings, specifications and the instructions of the Engineer, but excluding the cost of centering, shuttering, and reinforcement, but including the cost of admixture all complete as per drawings, specifications and instructions of the Engineer.</p>	cu.m	568.08			

[Handwritten signature]

[Handwritten mark]

[Handwritten signature]
 प्रमुख निर्माण अधिकारी
 नगर प्रशासन अधिकारी

Procurement Item Details

Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
10	FORM WORKS Supplying and laying centering, shuttering of various pattern formworks with 19 mm thick water proof ply wood & steel adjustable props for all kinds of RCC works for foundations, columns, shear walls, beams, slab, staircase, lintel, sill, pergola, including nails, propping scaffolding, staging, supporting and bracing in proper lines and level, sealing the joints with heavy duty brown self adhesive tape, aligning to line and levels including Ties, PVC Spacer, Providing openings/ cutouts/ pockets, applying De-shuttering chemical, De-shuttering as approved by the Engineer etc., complete at all levels as per drawing, specifications and instructions of the Engineer.	sq m	3150.0			
11	STEEL REINFORCEMENT Providing and fixing in position Fe 500 steel reinforcement of various diameter conforming to relevant IS code in R.C.C. works including straightening, cutting, bending, binding with 20 SWG annealed wire for tying the reinforcement bars at each junctions (binding wire shall not be measured separately) including all waste and cut pieces, provision for adequate numbers of spacers, chairs, providing and placing cement mortar (1:1) cover blocks to keep the bars in intended position at all levels all complete as per drawings, specifications and instructions of the Engineer. (Authorized lap length and for the bar length exceeding 10 meter in length shall be measured for the payment).	kg	113615.0			
12	FLOORING AND FINISHING WORKS 75 mm thick P.C.C. in (1:2:4) with cement punning (1:1) for flooring work with approved floor hardener (Dreitol FH or equivalent floor hardener) with approved quality cement, sand & aggregate 12mm and down grade including mixing, laying curing all complete work as per specification	Sqm	978.0			

प्रमाण निधि तिथि
 १०८३ १०८३ १०८३

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
13	Glazed tile on wall Providing and Laying 6mm.th. porcelain glazed/non glazed tiles on walls and floor of approved colored laid with cement sand mortar (1:4) finished with white cement including polishing all complete as per specification and instruction of site Engineer.	Sqm	200.0			चन्द्रनिवासपुर, कैलाल मधेश प्रदेश, नेपाल
14	Non-glazed tile on floor Providing and Laying 6mm.th. porcelain glazed/non glazed tiles on walls and floor of approved colored laid with cement sand mortar (1:4) finished with white cement including polishing all complete as per specification and instruction of site Engineer.	sq m	40.21			
15	Marble Flooring: Providing and Laying 16mm.th. on floor of approved colored laid with cement sand mortar (1:4) finished with white cement including polishing all complete as per specification and instruction of site Engineer.	sq m	15.1			
16	Epoxy Double Coat: Providing roviding and Laying all complete as per specification and instruction of site Engineer.	sq m	233.0			
17	Mosic Flooring 1:2:4 @ 20 MM:Providing and Laying including polishing all complete as per specification and instruction of site Engineer.	sq.m	362.95			
18	PLASTERING WORKS 12.50mm. Th. Cement sand plaster (1:4)work on ceiling surface of good finish in perfect line level and plumb including grooving in plaster wherever shown in drawings including chiselling racking the joints, wetting the surface and curing the work all complete as per specification and construction of the consultant/engineer all complete	sq.m	1400.0			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 किरण मिश्र निवास
 राज पासाकोट कैलाल

Procurement Item Details						
Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
19	PLASTERING WORKS 12.50mm Th. Cement sand plaster (1:4)work on building inner and outer surface of good finish in perfect line level and plumb including grooving in plaster wherever shown in drawings including chiselling racking the joints, wetting the surface and curing the work all complete as per specification and construction of the consultant/engineer all complete	sq.m	1657.58			मधेश प्रदेश, नेपाल
20	3/4X1.5" thick pani patti in cement sand mortar(1:3) in cantiliver portion of slab in perfect line and level racking the joints, wetting the surface and curing the work all complete as per specification and construction of the consultant/engineer all complete	rm	100.0			
21	CEMENT SKIRTING Providing, laying and curing 100 mm height and 18 mm thick Cement Plaster Skirting with C. M. 1:3 (1 Cement :3 Coarse sand), on perfect line & level, finished with a floating coat of neat cement including rounding of junctions and slanted finish at top in 45 degree, as per design, specification and instruction of the Engineer, all complete.	rm	150.0			
22	DOOR/WINDOW FRAME UPVC 100*60 mm for both windows and door with double glazing and Pivotable. Supply and Installation all complete as per drawings and instruction of site Engineer	sq.m	125.95			
23	RAILING WORK Supply, weilding & fabricating MS pipe railing with redoxide paint all complete as per specification and instruction.	Kg	746.0			
24	MS GRILL Providing and laying, M.S.Grill (10mmx10mm solid square Rod) of approved pattern and manufacture finished with one coat of red lead primer as per drawing, specification and instruction of engineer, all complete.	sq.m	169.15			
3 Electrical machinery apparatus equipment and consumables						

किरण लिमिटेड
 प्रमुख प्रशासकीय अधिकारी

Procurement Item Details						
Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Distribution board 12 way SPN made of mild steel sheet double cover lockable Geco or eqvt. Flush type etc all complete.	set	5.0			मधेश प्रदेश, नेपाल
2	Distribution board 8 way SPN made of mild steel sheet double cover lockable Geco or eqvt. Flush type etc all complete	set	5.0			
3	Distribution board 4 way SPN made of mild steel sheet double cover lockable Geco or eqvt. Flush type etc all complete	set	4.0			
4	6-32 Amps SP MCB Geco, North west, ISI or eqvt. For light and power supply	no	80.0			
5	6-32 Amps DP MCB Siemens, Geco, Legrend or eqvt. For main	no	18.0			
6	(2*6+1*1.5) sq.mm multistrand flexible cu wire for main in 3/4" HDPE polythene pipe from sub DB to DB etc, all complete (2*6+1*1.5) sq.mm multistrand flexible cu wire for main in 3/4" HDPE polythene pipe from sub DB to DB etc, all complete	rm	110.0			
7	10 sq.mm 4 core unarmoured copper cable for main panel board to DB, through Polythene pipe etc, all complete	rm	110.0			
8	CIRCUIT CUM POINT WIRING General Service Light/Fan/Exhaust Fan/ Call bell Point Wiring Supply, installation, testing and commissioning of light point /fan point wiring from DB to various points with 2.5 sqmm multistrand flexible cu wire through 1/2" internal dia HDPE conduit concealed via junction box and switch as per drawing and specification including cost of circular box and junction box and switch. Notes : 1) Average lenght per point = 12.5m Approximately	Point	200.0			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 किरण विधि विचार
 मुख्य प्रशासकीय अधिकारी



Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
9	Power Socket Point Wiring Supply and installation of 16A universal power socket point wiring with 2*4+1*1.5 sq mm multistranded copper wires through pvc listy or 3/4" internal dia HDPE conduit concealed from DB to various points, junction box as per drawing and specification. [Note : Average lenght per point = 12.5 m Approximately]	point	80.0			मधेश प्रदेश
10	1 gang 1 way switch North west type eqvt.etc all complete. Supply,installation, interconnection,testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator,flexible wire to be installed in specified location and height all complete.	No	5.0			
11	1 gang 2 way switch North west type eqvt.etc all complete. Supply,installation, interconnection,testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator,flexible wire to be installed in specified location and height all complete.	no	8.0			
12	2 gang 1 way switch North west type eqvt.etc all complete. Supply,installation, interconnection,testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator,flexible wire to be installed in specified location and height all complete.	no	9.0			
13	3 gang 1 way switch North west type eqvt.etc all complete. Supply,installation, interconnection,testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator,flexible wire to be installed in specified location and height all complete.	no	9.0			

मधेश प्रदेश सरकार
मुख्य प्रशासक

Procurement Item Details						
Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
14	4 gang 1 way switch North west type eqvt.etc all complete. Supply, installation, interconnection, testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator, flexible wire to be installed in specified location and height all complete.	no	10.0			चन्द्रनिपाहाङ, रौतहट मधेश प्रदेश, नेपाल
15	6 gang 1 way switch North west type eqvt.etc all complete. Supply, installation, interconnection, testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator, flexible wire to be installed in specified location and height all complete.	no	30.0			
16	16/6 Amps combined S/socket flush type north west type or eqvt. Supply, installation, interconnection, testing and commissioning of following type of switch socket including metal box ,screws ,gripes clamp, regulator, flexible wire to be installed in specified location and height all complete.	no	70.0			
17	1x40 Watt Tubelight box fitting type Wipro/Philips/Ge or eqvt.	Set	90.0			
18	Dome light 8" with CFL Heavy carrier decorative or ISI eqvt. Etc all complete	Set	70.0			
19	Electrical bell musical type all set.	Set	10.0			
20	42" ceiling fan Almonard/Bajaj or eqvt.etc all complete. Supply, installation, interconnection, testing and commissioning and putting into operation of following size of sweep ceiling/exhaust fans as per drawing specification including the adjustment hanging rod and louvers for exhaust fan as required.	Set	30.0			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 निर्माण विधि विचार
 मन्त्रालय, काठमाडौं


Procurement Item Details

Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
21	9" exhaust fan Almond /Rajaj or eqvt.etc all complete. Supply, installation, interconnection,testing and commissioning and putting into operation of following size of sweep ceiling/exhaust fans as per drawing specification including the adjustment hanging rod and louvers for exhaust fan as required.	set	7.0			चन्द्रनिमहिष, सधेश प्रदेश, कैलाल
22	4mm2 2 core Armored cable wire through 40mm dia HDPE Conduit(4kgf/cm2)	Rm	60.0			
23	3 mtrs Street light pole Supply,Installation and assembling,erection,connecting, testing and commissioning of the following External light fixtures complete with all accessories as required.	nos	2.0			
24	60/100 Main Panel board made of mild steel sheet double cover floor mount suitable color push type lock suitable size for housing the following items, all complete.12"*36"*48" size (space for 5 no MCCB)	set	1.0			
25	60 TP MCCB Siemens,Ge, Legrand or eqvt. for incoming for sub panel board.	set	3.0			
26	20-30-40 TP MCB Siemens,Ge, Legrand or eqvt. for outgoing for sub panel board.	set	4.0			
27	Voltmeter 0-500 v with selector switch all complete	set	2.0			
28	Indicator lamp with fuse all complete	set	3.0			
29	Ammeter 0-500 A with selector switch all complete	set	1.0			
30	Selector switch all complete	set	1.0			
31	CT coil of suitable ratio all complete	set	3.0			
32	16 A TP 25 KA MCB Siemens, Ge,Legrand or eqvt. for motor pump.	set	1.0			

Handwritten signature/initials.

Handwritten signature/initials.

Handwritten signature/initials.
 किरण निधि तिवारी
 प्रमुख प्रशासकीय अधिकारी

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
33	Earthing with cu plate size 65 cm x 65 cm x 3.15 mm with G. N. 8 cu wire for earth continuity from panel board to earthing site all complete with necessary accessories: salt, coal, cu plate, HDPE polythene pipe etc) as per specification and instruction of site engineer.	Set	1.0			
34	Supply, installation & testing of Air Termination Unit of 2m long solid copper rod of 16mm dia. to be mount on the roof of the building.	set	1.0			
35	Supply, installation & testing of 25mmx3.15 mm copper strip for horizontal conductor, duly brazed to lightning arrester & to be laid on roof of the building.	Rm.	2.0			
36	Supply, installation & testing of 25x3.15 Sq. mm copper strip for down conductor, duly brazed to horizontal conductor & to be clamp from horizontal conductor to the test point of the earthing.	Rm.	6.0			

4 Sewage- and refuse-disposal services sanitation and environmental services

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Indian pattern Commode with PVC low level flushing cistern and seat cover all complete set.	set	6.0			
2	580 mm Porcelain clay white glaze Orissa Pan (Hindware, Parryware, Classica, bolan or equivalent.)	set	4.0			
3	Indian pattern Porcelain clay white glaze Oval Wash Basin 50x40cm with mixer (jaquar, parryware, or equ. All complete set	set	5.0			
4	15mm CP Bib Cock	No	10.0			
5	15mm Auto closing bib cock with aerator	no	10.0			
6	C.P. 15mm dia Angle valve.	no	12.0			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
किरण निधि तिवारी
 प्रमुख प्रशासकीय अधिकृत

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
7	15mm two way angle valve	No	30.0			
8	15mm C.P commode spray with 1.2 m. long flexible pipe.	No	10.0			
9	CP Toilet Paper Holder heavy	no	10.0			
10	PVC Floor Trap 11*7.5cm (4" *2.5")	No	20.0			
11	Grab bar European standard	no	1.0			
12	CP Soap tray	Set	10.0			
13	Stainless steel towel rod 1.5 *45cm (1/2"*18")	Set	6.0			
14	Looking mirror Modi guard 450*600mm (18"*24")	No	6.0			
15	Foldable Hinge	No	5.0			
16	Water filter with UV lamp and filter media, 1 lit/min(Euro Guard or eqv) with complete set.	Set	5.0			
17	Pressure sensor switch for pump auto switch with all complete set. (Italian or eqv)	Set	3.0			
18	5 kg fire extinguisher ABC type Minimax, all complete set eversafe or equivalent .	Nos	5.0			
19	15 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS. 28.1kg/cm2 (flowguard or ISI Standard.)	Rm	153.0			
20	20 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS. 28.1kg/cm2 (flowguard or ISI Standard.)	rm	153.0			
21	25 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS. 28.1kg/cm2 (flowguard or ISI Standard.)	rm	153.0			
22	32 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS. 28.1kg/cm2 (flowguard or ISI Standard.)	rm	82.0			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 किरण निधि तिवार
 प्रमुख प्रशासकीय अधिकारी

Procurement Item Details						
Sl. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
23	40 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS. 28.1kg/cm ² (flowguard or ISI Standard.)	rm	453.0			१०५५०००.०० पञ्चविंशतिहजार, दशसहस्र मध्यम प्रदेश, विमान
24	15 mm dia CPVC Ball Valve, CTS Socket all complete	Nos	12.0			
25	20 mm dia CPVC Ball Valve, CTS Socket all complete	Nos	12.0			
26	25 mm dia CPVC Ball Valve, CTS Socket all complete	nos	12.0			
27	32 mm dia CPVC Ball Valve, CTS Socket all complete	nos	12.0			
28	40 mm dia CPVC Ball Valve, CTS Socket all complete	nos	12.0			
29	G.M. 25mm float valve	Nos	3.0			
30	1000 ltr. Stainless steel water tank (304 grade steel) fitting with all complete.	Nos	1.0			
31	2000 ltr. Stainless steel water tank (304 grade steel) fitting with all complete.	no	1.0			
32	50mm PVC pipe of 6 kg/cm ²	Rm	156.0			
33	75mm PVC pipe of 6 kg/cm ²	rm	156.0			
34	110mm PVC pipe of 6 kg/cm ²	rm	122.0			
35	50mm dia UPVC 90 degree bend	Nos	16.0			
36	50mm dia UPVC 45 degree bend	Nos	20.0			
37	75mm dia UPVC 45 degree bend	nos	22.0			
38	75 mm dia UPVC vent cowl	Nos	16.0			
39	75 mm dia UPVC Y-Brance	Nos	16.0			
40	75 mm dia pipe clip.	Nos	16.0			
41	110 mm Bend 45 degree bend	Nos	52.0			
42	75 mm dia UPVC plain/door Tee.	Nos	52.0			

१०/११

१०/११

१०/११
१०/११
१०/११

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
43	75 mm dia UPVC 90 degree bend	Nos	20.0			
44	110 mm dia UPVC vent cowl	nos	52.0			
45	110 mm dia UPVC plain door Tee	Nos	52.0			
46	110 mm dia UPVC 90 degrees bend	nos	52.0			
47	110 mm dia Y-Brance	nos	61.0			
48	110 mm dia UPVC pipe clip.	nos	61.0			
49	75*75 mm dia PVC p-trap	nos	52.0			
50	110*110 mm dia. PVC p-trap	nos	48.0			
51	2 HP Electric motor water pump multi stage coupled pump .	Nos	1.0			
52	Tank holding structure as instructed by Site Engineer	Nos	1.0			
53	CI Tank cover 24"*24" (50 kg) Square (Locking type)	Nos	1.0			

5 Construction work

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Painting on Interior Wall surface with two coats of plastic emulsion paint over one coat of primer to give uniform coloring and quality floss finish after proper surface preparation and Primer all complete as per drawing, specification and instruction of the Engineer, all complete.	sq.m	2200.0			
2	flexible iron channel gate as instructed by Site engineer	sq.m	30.0			
3	False Ceiling Supplying and Installation of 12.5mm thick Gypsum board False Ceiling with GI framing at gang ways/ passages and all accessories complete as per drawing, specification and instruction of the consultant/ Engineer all complete	sq.m	558.23			

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 प्रमुख प्रशासकीय अधिकारी
 नगर कार्यपालिकाको कार्यालय